

CONCRETE SURFACE PREPARATION



URETHANE DECK COATING REMOVAL



Beginning concrete profile



Completed concrete profile

- PROJECT** Exterior Concrete Parking Deck, approximately 28,000 sq. ft, Richardson, TX
- SERVICE** Concrete Surface Preparation—Coating Removal and Surface Prep for new urethan coating
- PROBLEM** Owner had a failing urethane coated upper deck that was leaking into spaces below. TCR hired by waterproofing contractor to strip all the coating from the deck and provide a clean profiled surface ready to accept a new traffic coating.
- SOLUTION** Used ride on scrapers followed by PCD diamonds on walk behind grinders. Hand ground all edges where machines would not reach. Shot blasted to CSP 3 profile and vacuumed clean for customer to install new deck coating.